





Additional Supplemental Environmental Project (SEP) Funding

for Santa Ana Sucker Habitat Project



SAWPA Commission January 19, 2016

Recommendation

That the Commission authorizes staff to enter into an agreement to receive approximately **\$39,000** in Supplemental Environmental Project (SEP) funding from a Santa Ana Regional Water Board fine levied on the City of Norco.







Background

- Briefed Commission on Feb 17, 2015; June 16, 2015; July 7, 2015
- Sucker Fish
 - Listed as "threatened" by US Fish & Wildlife
 - Likes Cobble/Rocks
- Santa Ana Sucker Conservation Team
 - City of RiversideOCWD























K:\Interns\Sam\RiverwalkStuff\Riverwalk2014.mxd SW-2433

Agreements for Project





 2: SAWPA – Regional Water Board and City of Beaumont



&

Water Boards

Water Boards



• \$37K

• \$24K

Project Deliverables

- Same for Beaumont and Norco Agreements
- Evaluation of pre and post project conditions for USFWS Agreement





Recommendation

That the Commission authorizes staff to enter into an agreement to receive approximately **\$39,000** in Supplemental Environmental Project (SEP) funding from a Santa Ana Regional Water Board fine levied on the City of Norco, with approval, subject to minor edits by the City of Norco, if needed.





Supporting Information

Line Item	Regional Board and US Fish and Wildlife Service Funding*	Further Detail
Hydrologist	\$4,000	Assumes \$125/hour
Biologist	\$8,000	Assumes \$125/hour
Permitting (408 Permit with Army Corps)	\$4,000	Assumes \$125/hour
Permitting Contingency	\$4,000	Assumes \$125/hour
Biological Monitoring	\$8,000	Assumes \$100/hour
Heavy Equipment, Equipment Operators, Fuel	\$44,000	Heavy equipment may include dump truck(s), backhoe(s)
Rock and Substrate Material Contingency	\$10,000	Assumes rock agreement with SBVWMD; \$35/quarter ton (funds from other sources augment costs)
Heavy Equipment Contingency	\$8,000	Heavy equipment may include dump truck(s), backhoe(s)
Project Implementation Development (site planning, access, agreements, etc).	\$10,000	Assumes \$125/hour
Total	\$100,000	

*This includes \$37,000 from the US Fish and Wildlife Service Carlsbad Office, \$24,000 from the City of Beaumont and \$39,000 from the City of Norco through the Regional Water Board Supplemental Environmental Project agreements.

Task/Subtask		2016									2017											2018														
rasky Subtask		F	Μ		A	М	J	J	Α	S	0	Ν	D	J	F	М	Α	М	J	J	Α	S	0	Ν	D	J	F	М	Α	М	J	J	A	S	0	N
Project Management Project Management Contract with Regional Board Submittal of Quarterly Reports																																				
Implementation Project Implementation Plan Rock Location in River (Heavy Equipment)																																				
Monitoring Biological and Water Quality Monitoring																																				

Inland Empire Brine Line Reach V Rehabilitation and Improvement Project

> Item 5.B January 19, 2016


Recommendation

Authorize the GM to approve:


- Change Order 2 to Task Order VALI326-02 with <u>Vali</u> <u>Cooper and Associates</u> for additional Construction Management and Inspection Services for the Project for an amount not to exceed **\$562,344**;
- Change Order 1 to Task Order DUDK326-02 with <u>Dudek</u> for additional Engineering Services during Construction for the Project for an amount not to exceed **\$64,420**; and
- Change Order 2 to Work Order No. 2016-16 with <u>Ramtech Laboratories</u> for additional CIPP Laboratory Testing for the Project for an amount not to exceed \$53,428.



Project Description and Location



2015 Googli





Current Work Activities

Reach 2 Shutdown

- Install MAS for Reach 2 by-pass
- CCTV / clean / laser profile (I15)
- Liner 1 and 9 Investigate / repair rope burn
- Liner 4,5 Repair Wrinkle
- Liner 16 Repair blow off connection and pressure test
- Liner 14 Remove and Replace 180 feet



Additional CM Services due to Contractor Delays


Contract Duration 400 Days, with Contract Completion of 2/8/16 Contractor's Recent Schedule Update - Completion Date of 8/6/16 (159 Days) 60% of Contract Work Remaining Additional Inspection Costs due to Contractor Delays \$430,790 Liquidated Damages \$5,000 / day




Additional CM Services due to Contractor Delays

		Completed	Remaining	%
	Activity	(Original Budget)	(Additional Budget	<u>Remaining</u>
-	CIPP Liner Installation (ft)/(Installs	s) 12,085 feet (16)	13,950 feet (19)	54%
•	Install by-pass system	12,085 feet	13,950 feet	54%
•	Remove by-pass system	0	26,032 feet	100%
•	CCTV/Laser Profiling/Cleaning	36,255 feet	41,850 feet	54%
•	Auger Boring	0	95 feet	100%
•	Receiving and Jacking Pits	0	4	100%
•	Install MAS Structures	10	9	47%
•	Install CIPP Access Pits	8	9	53%
	Install AV and BO Assemblies	14	18	56%
•	Construct Test Pits	0	3	100%

Hours





CIPP Installation Timeline

Estimated Installation Time (22 hrs.)



CIPP Segment

Additional CM Services due to **Liner Repairs** Liner repairs completed - \$14,060 - In - pipe repairs liners 11 - 16 Liner repairs pending - \$105,930 - Reline liners 11 - 13 Remove and replace portions of 14 – 16 Not included in original CM budget

CM and Inspection Services

Vali Cooper and AssociatesOriginal Contract Amount:

Change Order 1:

Change Order 2:

- Additional Inspection
 Due to Contractor Delays
- Extended Time for CIPP
 Liner Installations (Liner 1-7 and 9)
- Liner Repairs Completed
- Liner Repairs Pending
 - Total Change Order 2
- Amended Contract Amount:

\$818,610 \$64,255

\$430,790

\$11,564

\$14,060 \$105,930

<u>\$562,344</u>

\$1,445,209

Engineering Services During Construction

Dudek prepared project plans and specifications

Engineering Services during construction

- RFI / Submittal review
- Design deviations
- Video review
- Archeological monitoring

- Change assistance
- Progress meetings
- Field visits
- g Closeout activities

Additional services provided due to following

- Delay in schedule
- Remediation of liners
- PVC pipe installation
- Substitution of subcontractors
- Changes in material supplier

Engineering Services During Construction

Original

	Onginal	
<u>Task</u>	Scope of Work	<u>Actual</u>
– RFI's	20	49
 Submittals 	25	209
 Re-submittals 	25	90
 Progress Meetings 	15	37
 Review video 	37,000 ft	60,000 ft

 Additional services necessary to continue to provide Engineering Services during Construction

CIPP Laboratory Testing

- Ensure liner meets minimum physical properties per the specifications
- Per specifications, laboratory used for testing is recommended by Contractor and approved by SAWPA
- Ramtech Laboratories
 - Accredited laboratory for CIPP Testing
 - Located in Paramount, CA

CIPP Laboratory Testing

- Original budget anticipated consistency of lab results and exceeding requirements (\$50,000)
- Additional budget necessary to fully test all samples for each liner installed (\$53,426)
 19 liner segments remaining



Recommendation

Authorize the GM to approve:

- Change Order 2 to Task Order VALI326-02 with <u>Vali</u> <u>Cooper and Associates</u> for additional Construction Management and Inspection Services for the Project for an amount not to exceed **\$562,344**;
- Change Order 1 to Task Order DUDK326-02 with <u>Dudek</u> for additional Engineering Services during Construction for the Project for an amount not to exceed **\$64,420**; and
- Change Order 2 to Work Order No. 2016-16 with <u>Ramtech Laboratories</u> for additional CIPP Laboratory Testing for the Project for an amount not to exceed \$53,428.

Questions?